



## construction section 01

### A93 Rosenheim-Kiefersfelden

#### Data and facts

Company	ÖBA - Österreichische Betondecken Ausbau GmbH
Type	Concrete slab construction
Runtime	08.2017 - 09.2017
Principal	HABAU Hoch- und Tiefbaugesellschaft mbH

[Project report online](#)

[www.porr-group.com](http://www.porr-group.com)



# A concrete pavement textured with artificial turf.

The new concrete slab, manufactured using slipform construction, extends over roughly 62,500 m<sup>2</sup>. It is 12 to 15 m wide and 26 cm thick. Artificial turf was used to produce its surface structure: a total of around 20,000 running metres of joints were cut and sealed using a cold-sealing compound.

The company's own construction site mixing equipment, with an average mixing capacity of 200m<sup>3</sup>/h, provided around 17,500m<sup>3</sup> of road concrete for this project.

## Impressions



## Image notes

1

Getting there, piece by piece.

The construction joint has been prepared and now the concreting work can begin.

2

A professional set-up.

The fully-assembled Wirtgen SP500 slipform paver demonstrates its abilities: producing the hard shoulder near the three-way intersection at Inntal.

3

The foundations have been laid.

The surface of the approximately 62,500 m<sup>2</sup> concrete slab was textured using artificial turf.

Do you have questions about the project or would you like to learn more? Feel free to contact us for further information.

4

Highlighting the sideshow.

ÖBA's infrastructure has been perfectly set up on-site to guarantee efficient work and rapid completion.

**PORR AG Group Communications**

Absberggasse 47

1100 Wien

T +43 50 626-0

E-Mail: [comms@porr-group.com](mailto:comms@porr-group.com)